11'-0"

OIL LINE DIA. xxx"

POWER UNIT
48"W x 24"D x 48" H

OIL LINE DIA. xxx"

POWER UNIT
48"W x 24"D x 48" H

8"x 8" BLOCKOUT REQ'D,
IN WALL FOR OIL LINE
COORDINATE LOCATION
WITH MECO SUPERVISOR

CONTROLLER
36"x 8"x 32"

CONTROLLER
36"x 8"x 32"

NOTE:
18" CLEARANCE FOR
MAINTENANCE IN
FRONT OF UNIT AND
MUFFLER SIDE

NOTE:
MACHINE ROOM
CEILING HT.
7'-0" MINIMUM

TWO SETS OF 1P. & 3P. DISCONNECTS,
ONE SET PER ELEVATOR BY G.C.
SERVICE REQ'D / SERVICE AMP XXX AMP
FULL LOAD AMP / RUNNING LOAD XXX AMP

LIGHT SWITCH AND
LIGHTS BY G.C.

3'-0"x 6'-8"
CLEAR OPEN

9'-0"

DULPLEX MACHINE ROOM